



THE CRICKET ASSOCIATION OF BENGAL

DR. B.C. ROY CLUB HOUSE, EDEN GARDENS, KOLKATA-700 021

Ref. No. 163(4)/33/4098/2025

2nd September 2025

NOTICE

THE CRICKET ASSOCIATION OF BENGAL is inviting sealed quotation from interested parties for the following job.

A. 1st & 2nd floor toilets & 2nd floor hall civil & renovation of NCC building at Eden Gardens Kolkata.

Please refer details BOQ from the website of the Association

([https // www.cricketassociationofbengal.com](https://www.cricketassociationofbengal.com))

Time for the completion of job shall be 1 month from the date of issue of work order.

The interested parties should submit the quotation to The Association (The Cricket Association of Bengal DR. B .C. Roy Clube House Eden Gardens Kolkata – 700 021) within 5th September 2025 before 6.00 PM. The parties must visit the site and understand the scope of work before submission of rates.

Naresh Ojha
Hony. Secretary

BOQ for NCC Building Bathroom 1st Floor and 2nd Floor

Sl No	Description	QTY	UOM	Rate/ unit	Amount
1	Dismantling Tiles with cement mortar & Brick wall	2732.00	Sft		
2	Made new 125mm thick Brick Wall	450.00	Sft		
3	Open out existing materials and Groove cutting for Pipe line & Swage line	2.00	Nos		
4	Providing & laying 50mm thick UPVC pipe with necessary require fittings.	120.00	Rft		
5	Providing & fixing Sweage & waste line .	2.00	Lot		
6	Cost of providing & fixing Brass Gate Valve.	2.00	Nos		
7	Cost of laying 20mm thick CPVC water Pipe line with necessary fittings like Tee, Elbow, MTA, FTA, etc comp.	360.00	Rft		
8	Cost of 20mm thick plastering with cement mortar	1,832.00	Sft		
9	Cost of PCC on the Floor with sand, cement & stone chips	680.00	Sft		
10	Cost of made new 32mm thick PVC pipe for main line with necessary require fittings complete.	80.00	Rft		
11	Cost of providing & fixing (2'x1') wall Tiles at bathroom with groove filling & under bedding tiles mortar complete.	1484.00	Sft		
12	Providing & Fixing of (600 x 600)mm Floor Tiles with under bedding materials.	720.00	Sft		
13	Cost of made new UPVC Door.	2.00	Nos		
14	Providing & fixing new Pressmatic Basin Pilarcock (Jaquar)	6.00	Nos		
15	Cost of providing & fitting 24" Connector Pipe.	26.00	Nos		
16	Cost of Providing & fixing Basin with Waste AIS-WHT-101901	6.00	Nos		
17	Cost of Providing & fixing Magic Pipe.	14.00	Nos		
18	Cost of providing & fixing Angular stop cock with extention Piece & CP Flange. (SQT505NKN) (Essco)	18.00	Nos		
19	Cost of provide & fixing (2'x2') Mirror with necessary material	6.00	Nos		
20	Cost of providing & fixing Soap Dispencer	4.00	Nos		
21	Cost of providing & fixing 2 in 1 CP Bib cock with Extention Piece & Flange complete. (SQT512ANKN) (Essco)	8.00	Nos		
22	providing & fixing of PVC Health Foucet.	8.00	Nos		
23	Providing & fitting 32mm metropole flash Valve with materials, Pipe etc complete. (Jaquar)	8.00	Nos		
24	Providing & fitting EWC with Anchore Bolt As discussed Model- ORS105941NPP (Essco)	8.00	Nos		
25	Providing & fixing new pressmatic angel Valve with necessary require materials as require.	8.00	Nos		
26	Providing & fixing Urinal with necessary bracket (Model: -URS-WHT-13261H) (Jaquar)	8.00	Nos		
27	Providing & fitting Urinal Connector C.P.	8.00	Nos		
28	Providing & fixing CP sprader for Urinal Area	8.00	Nos		
29	Providing & fixing Urinal Waste	8.00	Nos		
30	Providing & fixing CP Grating.	12.00	Nos		
31	Providing & fixing Granite Partition for Urinal.	6.00	Nos		
32	Providing & fixing 3 in 1 CP Wall Mixer (Bend Pipe) (Jaquar) Cont	6.00	Nos		
33	Cost of CP Shower Arm	6.00	Nos		
34	Cost of CP 4" Over Head Shower.	6.00	Nos		
35	Cost of CP Soap Dish (Duragres)	6.00	Nos		
36	Cost of Water Heater 10 Ltr (Venus)	6.00	Nos		
37	Cost of made new Black Stone for Basin under counter.	120.00	Sft		

38	providing & fixing 12mm to 15mm thick Black Granite with moulding including under materials mortar complete.	91.00	Sft		
39	Providing & fixing Black granite Border along with the wall, step, noising and Door all as per direction with 4" skirting	110.00	Rft		
40	Cost of made new HPL Board partition with necessary require SS 304 grade fittings as per approved colour for EWC Panel & shower area Door (Brand Merino)	14.00	Units		
41	Laying Putty on the wall & ceiling	1400.00	Sft		
42	Applying painting with scraping complete	2700.00	Sft		
43	Cost of providing & fixing Gypsum Board False ceiling	700.00	Sft		
44	Cost of made new UPVC openable Window (4'x3')	4.00	Nos		
45	Cost of debris removal from 1st floor to gr Floor.	2.00	Lot		
46	Transporation Cost of materials.	2.00	Lot		
TOTAL					

Sub: - NCC building 2nd Floor Civil painting work Work.

Sl.No.	Description	Qty	Uom	Rate/Unit	Amount
1	Cost of remove existing aluminium frame with partition.	513	Sqft		
2	Remove existing damage wooden Window with Frame.	18	Nos		
3	Cost of made new Brick wall for platform.	5	Nos		
4	Cost of made new Aluminium annodised window with 5mm thick Glass including all require materials.	220	Sqft		
5	Cost of Civil messonary Repair with cement mortar.	18	Nos		
6	Cost of refabrication of window Grill.	18	Nos		
7	Cost of providing & fixing new Window Vertical Blinds as per approve colour with necessary require materials.	220	Sqft		
8	Cost of laying Putty on the existing damage area.	1	Lot		
9	Cost of applying One coat primer & two coat paint on the wall & ceiling with scraping cleaning.	4200	Sqft		
10	Rabish remove & lifting of materials.	1	Lot		
